



**PIMA COUNTY  
PROCUREMENT DEPARTMENT  
DESIGN AND CONSTRUCTION DIVISION**  
130 W. CONGRESS STREET, 3rd FLOOR, TUCSON, AZ. 85701  
PHONE: (520) 724-3731 FAX: (520) 724-4434

March 31, 2016

**ADDENDUM No. 1**

**PROJECT: Mission Road Complex Fuel Island Project (XMRFLI)**

**SOLICITATION NO.: IFB 210864**

**TO ALL CONTRACTORS:**

The attached changes, clarifications and/or additions shall be incorporated to the above-referenced Invitation for Bid.

**Mission Road Complex Fuel Island Project, Addendum No. 1 prepared by Pima County Facilities Management, dated March 31, 2016 (2 pages).**

Any questions regarding this Addendum should be directed to Ana Wilber at [ana.wilber@pima.gov](mailto:ana.wilber@pima.gov).

Bidders must acknowledge receipt of this Addendum. Failure to do so **will** render the bid non-responsive.

All other specifications, terms and conditions, not specifically changed by this Addendum, shall remain the same.

*Ana Wilber*

Ana Wilber, CASPP, CPPB  
Commodity / Contracts Officer



# PIMA COUNTY

## FACILITIES MANAGEMENT


150 WEST CONGRESS, 3<sup>rd</sup> FLOOR  
TUCSON, ARIZONA 85701

LISA JOSKER, FMD

PH: (520) 724-3703 \* FAX: (520) 724-3900

### Mission Road Complex Fuel Island Project Bid Solicitation #210864 Addendum No. 1

Date: March 31, 2016



EXPIRES 12/31/2016

THIS ADDENDUM IS ISSUED TO MODIFY, EXPLAIN OR AMEND THE ORIGINAL DRAWINGS AND SPECIFICATIONS AND IS HEREBY MADE A PART OF THE CONTRACT DOCUMENTS. BIDDERS SHALL DETERMINE THE EXTENT OF WORK FROM THE DRAWING AND/OR SPECIFICATION ITEMS LISTED BELOW.

Addendum No. 1 incorporates the following plan and/or specification clarifications and changes to the original set of construction documents dated **January 06, 2016**.

I. Clarifications:

- a. Pima County shall be responsible for removing the existing office furniture in the vehicle bays of building no. 7 prior to the start of construction.
- b. Refer to D103 for the size and quantity of underground fuel tanks to be removed by the contractor.
- c. The existing asphalt can be used as a base course under the proposed concrete and asphalt. If the contractor elects to utilize this method of base course, then Section 303 of the latest edition of the PAG Standards must be followed for the use of recycled asphalt pavement for base course.
- d. Refer to drawing A202 for the quantity of bollards to be installed at the guard shack.
- e. The "U" bollards are included in both the base bid at the fuel island canopy and the additive alternate no. 1 at the vacuum canopy. Refer to specification section 012300- Alternates for a description of the alternates.
- f. Pima County will pay for the work associated with the new water service and fire line including any fees and permits. The Contractor shall be responsible for coordinating the work with Tucson Water.
- g. This project does not require "prevailing wages" or "Davis Bacon Wages".

- h. Pima County will contract with a materials testing entity and pay for the required materials testing and inspections required in the construction documents.
- i. Flexible double-contained pipe shall be direct bury; equal to UPP by APT Piping Containment.
- j. Warning decals shall installed be per the tank and fueling equipment manufacturer's standards.
- k. Drawing M10: The intent is to run 2.0" piping from the tanks to the dispensers. Only the dispenser risers will be 1-1/2" since the specified dispensers indicated on the drawings have a 1-1/2" inlet.
- l. Refer to keynote #5 on sheet M101 for the spill containment system for the fuel unloaded, any additional spill kits will be provided by owner.
- m. Per NFPA 30A-4.2.4, 'tanks that produce a gravity head on the dispensing devices shall be equipped with a device, such as a normally closed solenoid valve'. Provide anti-siphon/solenoid valve, pressure relief valve and emergency valve (fire valve) downstream of the submersible pump.

II. Changes to Drawings:

- a. Sheet SB002, VIII: Driller Caisson Notes E and H; unit costs associated with greater depths, slurry drilling and removable casings are no longer required. Refer to "Allowances" for bid requirements for slurry drilling and removable casings.

III. Changes to Specifications:

- a. Section 323113 2.2A1
  - i. Chain link fence fabric wire size shall be revised to 9 gauge.
- b. Section 231323-2.4-B-2 shall be omitted.
- c. 231113-2.4-B
  - i. Fiberglass pipe requirements shall be omitted.
- d. Section 231113-2.5B thru F and 2.7 A and B shall not apply if not referenced on the drawings.

IV. Documents Attached: none

THE BIDDER SHALL BE RESPONSIBLE FOR READING THIS ADDENDUM IN ITS ENTIRETY TO DETERMINE THE EXTENT OF CLARIFICATIONS AND /OR CHANGES INCLUDED IN THIS DOCUMENT AND SHALL INCORPORATE THE CLARIFICATIONS AND/OR CHANGES IN THE BID SUBMITTED TO PIMA COUNTY.

**END OF ADDENDUM NO. 1**