

SIGNING GENERAL NOTES:

THE FOLLOWING NOTES SHALL APPEAR ON ALL TRAFFIC SIGNAL PLANS AND ARE INCLUDED HERE FOR THE USER'S REFERENCE.

1. ALL EQUIPMENT, MATERIALS AND CONSTRUCTION SHALL MEET OR EXCEED THE REQUIREMENTS CONTAINED IN THE CURRENT CITY OF TUCSON /PIMA COUNTY (CDT/PC) STANDARD SPECIFICATIONS AND THE STANDARD DETAILS FOR PUBLIC IMPROVEMENTS, THE SPECIAL PROVISIONS AND THE APPROVED PLANS.
2. ALL SIGNS SHALL BE IN COMPLIANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE LATEST EDITION OF THE PIMA COUNTY/CITY OF TUCSON TRAFFIC SIGNING DESIGN MANUAL, THESE PLANS, AND THE SPECIAL PROVISIONS.
3. SIGNS MAY BE MODIFIED AND LOCATIONS ADJUSTED TO FIT CONDITIONS IN THE FIELD AT THE DISCRETION OF THE TRAFFIC ENGINEER.
4. THE DESIGN SPEED FOR THE ROAD IS _____ THE POSTED SPEED LIMIT IS _____ SIGN PLACEMENT SHALL BE BASED ON THE POSTED SPEED LIMIT.
5. POST LENGTHS INDICATED ON SIGN SUMMARY SHEETS ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY ACTUAL POST LENGTHS.
6. ALL PERFORATED POSTS SHALL BE INSTALLED IN A CONCRETE FOUNDATION, UNLESS OTHERWISE DIRECTED BY THE TRAFFIC ENGINEER.
7. ALL SIGN STATION LOCATIONS ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY ACTUAL SIGN LOCATIONS WITH THE TRAFFIC ENGINEER PRIOR TO THE INSTALLATION OF ANY SIGNS.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL WORK WITH BLUE STAKE FOR INSTALLING ALL TRAFFIC SIGNS IN THE FIELD AND FOR MAINTAINING ALL SIGNING UNTIL PROJECT IS APPROVED FOR "CONSTRUCTION ACCEPTANCE" BY PIMA COUNTY (FULLY OPEN TO TRAFFIC, ALL PUNCH LIST ITEMS ARE COMPLETED, AND ONE YEAR WARRANTIES BEGIN).
9. ALL OVERHEAD MOUNTED SIGNS SHALL BE DIAMOND GRADE SHEETING, TYPE XI. ALL SCHOOL SIGNS SHALL BE FLORESCENT YELLOW/GREEN, DIAMOND GRADE SHEETING, TYPE XI. ALL OTHER SIGNS SHALL BE HIGH INTENSITY PRISMATIC SHEETING, TYPEIV. ALL GROUND MOUNTED SIGNS SHALL HAVE AN ANTI GRAFFITI COATING APPLIED TO SIGN FACE, 3M #1160 FILM OR EQUIVALENT.
10. ALL NEW SIGNS SHALL HAVE 0.080 GAUGE, RADIUS CORNER, ALUMINUM BACKING UNLESS OTHERWISE NOTED.
11. PRIOR TO DISTURBING ANY TRAFFIC SIGNS, A SIGN CONDITION INVENTORY OF ALL EXISTING SIGNING SHALL BE CONDUCTED BY THE CONTRACTOR AND PROVIDED TO THE PIMA COUNTY SIGN SHOP SUPERVISOR (520-724-2600). INVENTORY SHALL INDICATE CURRENT SIGN LOCATION AND CONDITION, INCLUDING ANY EXISTING DAMAGE OR DEFICIENCIES.
12. ANY SIGNS AND POSTS BEING RE-USED ON THIS PROJECT SHALL BE STOCKPILED IN A MANNER TO AVOID DAMAGE AND MAINTAIN THE INTEGRITY OF THE SIGNS. SAFE STORAGE OF STOCKPILE AND PAYMENT FOR DAMAGE TO THE STOCKPILE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
13. ALL SIGNS AND POSTS NOT BEING RE-USED ON THIS PROJECT SHALL BE DISMANTLED, STACKED AND DELIVERED TO THE OWNER (CITY OR COUNTY) BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR THE SAFE STORAGE AT THE CONSTRUCTION SITE UNTIL DELIVERY, AND THE SAFE UNLOADING OF THE SALVAGED MATERIAL. NOTIFICATION OF DELIVERY SHALL BE MADE AT LEAST 2 WORKING DAYS PRIOR TO DELIVERY. PIMA COUNTY SIGN SHOP. PIMA COUNTY SIGN SHOP 1313 S. MISSION ROAD (520-724-2631). NO FRIDAY DELIVERIES.

Call at least two full working days before you begin excavation.



Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Priscilla S. Cornelia, P.E., Director

Designed	Date
Drawn	
Checked	
POST. Eng.	

No.	Revision Description	Engineer	Date

Pima County Department of Transportation

SIGNING GENERAL NOTES

Shannon Road - Ina Road to Magee Road - Project No. 4XXXXX