



**PIMA COUNTY
PROCUREMENT DEPARTMENT
DESIGN AND CONSTRUCTION DIVISION**

130 W. CONGRESS STREET, 3rd FLOOR. TUCSON, AZ. 85701
PHONE: (520) 724-3731 FAX: (520) 724-4434

August 12, 2016

ADDENDUM NO. 07

PROJECT: IFB 207424 – CONTINENTAL RANCH REGIONAL PUMP STATION
REHABILITATION PROJECT No. 3CRS05

TO ALL CONTRACTORS:

Be advised of the additions, clarifications and/or changes to the above-referenced Invitation for Bid as stated in the following Addendum.

1. The *Bid Due Date and Time* **ARE CHANGED TO** Thursday, September 1, 2016 at 2:00 p.m.
2. County has received additional questions and provides the questions and their answers as clarification.
 - Q. There is a Control Panel Enclosure Schedule on page 176 of 201 of the Special Revisions PDF that does not relate to any of the electrical drawings that I can find. Are these panels supposed to be included in the bid? If so, can you please provide the electrical drawings and/or panel layout for them?
 - Q. The drawing located directly after the Enclosure schedule show one panel (not named) where the contractor is to remove components. A few pages later it shows 2 panels that are almost identical (PS2 & PS3) that appear to match the "not named" panel where we are to remove components. Is it safe to assume that there will be two panels that the contractor will have to remove components from and rename the panels PS2 and PS3?
 - A. Keynote A on Drawing E30 references the "Pima County Standard SCADA Panel Specifications" (which are the EMA specifications and drawings referenced in the question), and notes that the Continental Ranch Upgrade Design contract drawings take precedence where there are differences. There are many differences, and EMA documents are referenced to cover general SCADA panel construction. Therefore, the panels shown in the "Pima County Standard SCADA Panel Specifications" are not to be provided for this job.
 - Q. There is a bid line item 4.8 labeled "Electrical wiring, conduit and appurtenances." Do we include ALL conduit, wiring for the entire project in this line item, and not in each of any other line item that would have conduit, wiring etc as part of a complete scope?

4

For example you also have a line item 4.11 "Fire alarm control panel and appurtenances." Do we include all FA devices, control panel, programming in this line item but NOT the conduit and wiring that are required for the FA? Or line item 4.3 "Exterior facility lighting including all fixtures and appurtenances." Do we include just the fixtures and installation but not the conduit, wiring etc. required for a complete scope?

- A. Line item 4.8 shall include all electrical wiring and conduit as required to bring the electricity up to each of the individual equipment items. All wiring and conduit internal to a piece of equipment shall be included within that equipment's line item.
- Q. Will all exterior light fixtures be included in line item 4.3 or do we include light fixtures in line item 4.5 which looks like it is the FMP Station?
- A. All exterior lighting shall be included within line item 4.3 "Exterior facility lighting including all fixtures and appurtenances."

Note: At least one additional addendum will be issued by County.

This addendum is a total of **2 pages**. There are no attachments to this addendum.

All other requirements and terms of the Solicitation remain unchanged. Respondents are required to certify receipt of this addendum in their Bid Proposal. Failure to do so may result in declaration of the bid as non-responsive.

Any questions regarding this addendum should be directed to keith.rogers@pima.gov or by fax to 520-770-4012.

Keith E. Rogers, CPPB
Contracts Officer