



NORTHBOUND BRIDGE PARAPET ELEVATION: WALKWAY SIDE
Scale: 1/8" = 1'-0"

Notes:

1. Refer to the Special Provisions for further requirements and information.
2. See Railing and Vista plans for more details on the parapet and railing integration.
3. The concrete parapet with railing combination, vista posts, and vista railing will be measured by the linear foot and paid for, complete in place, under Item 9330007 - Railing (Special).
4. Horizontal dimensions shown on plans do not take into account the vertical curvature or profile of the bridge.
5. The clear spacing of vertical railing members shall be less than 6" no less than 5 1/2".
6. The vertical members shall be plum after fabrication and installation.
7. Refer to the Bridge Plans for concrete parapet, vista post, and vista railing details.

CDR
www.creative设计resolutions.com
3413 Windom Road
Brentwood, MD 20722
phone: 301-699-0581

Pima County Department of Transportation

BRIDGE ART SHEETS

LA CHOLLA BOULEVARD BRIDGE
MAGEE RD. TO OVERTON RD.
PROJECT NO. 4R7ILM

STAGE IV
SUBMITTAL
PRELIMINARY
NOT FOR
CONSTRUCTION
OR
RECORDING

Priscilla S. Cornelio P.E., Director

No.	Revision Description	Engineer	Date
1	RESPONSE TO RFP 541		11/28/13

Designed	Drawn	Checked	Proj. Mgr.
DP	BM	ST	ES

Date
11/7/10
11/7/10
11/7/10
11/7/10

URS
333 East Wetmore, Suite 400
Tucson, AZ 85705
phone: 520-887-1800