

SIGNING GENERAL NOTES:

THE FOLLOWING NOTES SHALL APPEAR ON ALL SIGNING PLANS AND ARE INCLUDED HERE FOR THE USER'S REFERENCE.

1. ALL EQUIPMENT/MATERIALS AND CONSTRUCTION SHALL MEET OR EXCEED THE REQUIREMENTS CONTAINED IN THE CURRENT PIMA ASSOCIATION OF GOVERNMENTS (PAG) STANDARD SPECIFICATIONS AND STANDARD DETAILS FOR PUBLIC IMPROVEMENTS, THE SPECIAL PROVISIONS, THE SUPPLEMENTAL SPECIFICATIONS AND THE APPROVED PLANS. ALL SIGNING SHALL BE INSTALLED IN COMPLIANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND THE PIMA COUNTY/CITY OF TUCSON (PC/COT) SIGNING DESIGN MANUAL AND APPLICABLE AMENDMENTS.
2. THE SIGNING CONTRACTOR SHALL CONTACT THE PIMA COUNTY SIGNING SUPERVISOR AT (520) 724-2630 AT LEAST THREE (3) WORKING DAYS IN ADVANCE OF SIGN INSTALLATION TO SCHEDULE INSPECTION AND APPROVAL OF SIGN LOCATIONS. SIGN SHOP HOURS ARE MONDAY THROUGH THURSDAY 6:00 AM TO 3:30 PM, STATE HOLIDAYS EXCLUDED.
3. PRIOR TO DISTURBING ANY TRAFFIC SIGNS, A SIGN CONDITION INVENTORY OF ALL EXISTING SIGNING SHALL BE CONDUCTED BY THE CONTRACTOR AND PROVIDED TO THE PIMA COUNTY SIGN SHOP SUPERVISOR (520) 724-2630. THE INVENTORY SHALL INDICATE CURRENT SIGN LOCATIONS AND CONDITIONS, INCLUDING ANY EXISTING DAMAGE OR DEFICIENCIES.
4. SIGNS MAY BE MODIFIED AND LOCATIONS ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED AND APPROVED BY THE COUNTY ENGINEER OR THEIR DESIGNEE.
5. THE DESIGN SPEED FOR THE ROAD IS ____ MPH. THE POSTED SPEED LIMIT IS ____ MPH. SIGN PLACEMENT SHALL BE BASED ON THE POSTED SPEED LIMIT.
6. POST LENGTHS INDICATED ON SIGN SUMMARY SHEETS ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY ACTUAL POST LENGTHS.
7. ALL PERFORATED POSTS SHALL BE INSTALLED IN A CONCRETE FOUNDATION, UNLESS OTHERWISE DIRECTED BY THE COUNTY ENGINEER OR THEIR DESIGNEE.
8. ALL SIGN STATION LOCATIONS ARE APPROXIMATE, THE CONTRACTOR SHALL VERIFY ACTUAL SIGN LOCATIONS WITH THE PIMA COUNTY SIGN SUPERVISOR OR THE PIMA COUNTY INSPECTOR.
9. ALL SIGNS SHALL HAVE TYPE XI SHEETING OR AN EQUIVALENT. ALL WARNING SIGNS HAVING YELLOW BACKGROUNDS SHALL USE FLUORESCENT YELLOW SHEETING. ALL SCHOOL SIGNS SHALL USE FLUORESCENT YELLOW/GREEN SHEETING. ALL GROUND MOUNTED SIGNS SHALL HAVE AN ANTI GRAFFITI COATING APPLIED TO SIGN FACE, 3M #1160 FILM OR EQUIVALENT.
10. A 3"x2" PRESSURE SENSITIVE, UV RESISTANT LABEL INDICATING THE SIGN MANUFACTURER'S NAME AND DATE OF MANUFACTURE SHALL BE PLACED IN THE UPPER RIGHT CORNER OF THE BACK OF ALL SIGNS EXCEPT STREET NAME SIGNS AT THE TIME OF INSTALLATION. STREET NAME SIGNS SHALL INCLUDE A SIGN IDENTIFICATION DECAL AS SHOWN ON PIMA COUNTY SIGNING DETAIL 9-22A.
11. ALL NEW SIGNS SHALL HAVE 0.080 GAUGE, RADIUS CORNER, ALUMINUM BACKING UNLESS OTHERWISE NOTED.
12. UPON FINAL INSPECTION, A WRITTEN ACCEPTANCE OR ITEMIZED PUNCH LIST OF MISSING OR UNACCEPTABLE SIGN INSTALLATIONS SHALL BE SUBMITTED TO THE CONTRACTOR BY PIMA COUNTY.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL WORK WITH ARIZONA 811 FOR INSTALLING ALL TRAFFIC SIGNS IN THE FIELD AND FOR MAINTAINING ALL SIGNING UNTIL PROJECT IS APPROVED FOR "CONSTRUCTION ACCEPTANCE" BY PIMA COUNTY (FULLY OPEN TO TRAFFIC, ALL PUNCH LIST ITEMS ARE COMPLETED, AND THE ONE YEAR WARRANTIES BEGIN).
14. ANY SIGNS AND POSTS BEING RE-USED ON THIS PROJECT SHALL BE STOCKPILED IN A MANNER TO AVOID DAMAGE AND MAINTAIN THE INTEGRITY OF THE SIGNS. SAFE STORAGE OF STOCKPILE AND PAYMENT OF DAMAGE TO THE STOCKPILE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
15. ALL SIGNS AND POSTS NOT BEING RE-USED ON THIS PROJECT SHALL BE DISMANTLED, STACKED AND DELIVERED TO THE SIGN SHOP BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR THE SAFE STORAGE AT THE CONSTRUCTION SITE UNTIL DELIVERY AND THE SAFE UNLOADING OF THE SALVAGED MATERIAL. NOTIFICATION OF DELIVERY SHALL BE MADE AT LEAST TWO (2) WORKING DAYS PRIOR TO DELIVERY. THE PIMA COUNTY SIGN SHOP IS LOCATED AT 1313 S. MISSION ROAD (520) 724-2630. NO FRIDAY DELIVERIES.
16. THE PC/COT SIGNING MANUAL IS AVAILABLE ONLINE.



Ana M. Olivares, P.E., Director

Pima County Department of Transportation

Designed	Date
Drawn	10/08/2018
Checked	
Proj. Engr.	

No.	Revision	Description	Engineer	Date

SIGNING GENERAL NOTES:

Project Name - Xxxx Road to Xxxx Road - Project No. 4XXXXX