

**SIGNING GENERAL NOTES:**

THE FOLLOWING NOTES SHALL APPEAR ON ALL TRAFFIC SIGNAL PLANS AND ARE INCLUDED HERE FOR THE USER'S REFERENCE.

1. ALL EQUIPMENT/MATERIALS AND CONSTRUCTION SHALL MEET OR EXCEED THE REQUIREMENTS CONTAINED IN THE CURRENT PINN ASSOCIATION OF GOVERNMENTS (PAG) STANDARD SPECIFICATIONS AND THE STANDARD DETAILS FOR PUBLIC IMPROVEMENTS, THE SPECIAL PROVISIONS AND THE APPROVED PLANS. ALL SIGNING SHALL BE INSTALLED IN ACCORDANCE WITH THE PAVCOOT SIGNING DESIGN MANUAL AND APPLICABLE AMENDMENTS.
2. ALL SIGNS SHALL BE IN COMPLIANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE LATEST EDITION OF THE PINN COUNTY/CITY OF TULSA TRAFFIC SIGNING DESIGN MANUAL, THE PAG STANDARD SPECIFICATIONS, THE PINN COUNTY SUPPLEMENTAL SPECIFICATIONS, ANY REQUIRED SPECIAL PROVISIONS, AND THESE PLANS.
3. SIGNS MAY BE MODIFIED AND LOCATIONS ADJUSTED TO FIT CONDITIONS AT THE DISCRETION OF THE TRAFFIC ENGINEER.
4. THE DESIGN SPEED FOR THE ROAD IS ..... MPH. THE POSTED SPEED LIMIT IS ..... MPH. SIGN PLACEMENT SHALL BE BASED ON THE POSTED SPEED LIMIT.
5. POST LENGTHS INDICATED ON SIGN SUMMARY SHEETS ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY ACTUAL POST LENGTHS.
6. ALL PERFORATED POSTS SHALL BE INSTALLED IN A CONCRETE FOUNDATION, UNLESS OTHERWISE DIRECTED BY THE TRAFFIC ENGINEER.
7. ALL SIGN STATION LOCATIONS ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY ACTUAL SIGN LOCATIONS WITH THE TRAFFIC ENGINEER PRIOR TO THE INSTALLATION OF ANY SIGNS.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL WORK WITH ARIZONA 401 FOR INSTALLING ALL TRAFFIC SIGNS IN THE FIELD AND FOR MAINTAINING ALL SIGNING UNTIL PROJECT IS APPROVED FOR CONSTRUCTION ACCEPTANCE BY PINN COUNTY (CALL OPEN TO TRAFFIC, ALL PUNCH LIST ITEMS ARE COMPLETED, AND ONE YEAR WARRANTIES BEGINS).
9. ALL SIGNS SHALL HAVE TYPE 31 SHEETING OR AN EQUIVALENT. ALL WARNING SIGNS HAVING YELLOW BACKGROUNDS SHALL USE FLUORESCENT YELLOW SHEETING. ALL STOP SIGNS SHALL USE FLUORESCENT YELLOW/GREEN SHEETING. ALL GROUND RELATED SIGNS SHALL HAVE AN ANTI GRAFFITI COATING APPLIED TO SIGN FACE, 3M 8106 FILM OR EQUIVALENT.
10. A 2" X 4" PRESSURE SENSITIVE UV RESISTANT LABEL INDICATING THE SIGN MANUFACTURER'S NAME AND DATE OF MANUFACTURE SHALL BE PLACED IN THE UPPER RIGHT CORNER OF THE BACK OF ALL SIGNS, EXCEPT FOR STREET NAME SIGNS. AT THE TIME OF INSTALLATION, STREET NAME SIGNS SHALL INCLUDE A SIGN IDENTIFICATION DECAL AS DESCRIBED WITHIN PINN COUNTY SIGNING AND MARKING STANDARDS DETAIL 611.
11. ALL NEW SIGNS SHALL HAVE 8000 GAUGE, RADIUS CORNER, ALUMINUM BACKING UNLESS OTHERWISE NOTED.
12. PRIOR TO DESTROYING ANY TRAFFIC SIGNS, A SIGN CONDITION INVENTORY OF ALL EXISTING SIGNING SHALL BE CONDUCTED BY THE CONTRACTOR AND PROVIDED TO THE PINN COUNTY SIGN SHOP SUPERVISOR (500 724-2630). INVENTORY SHALL INDICATE CURRENT SIGN LOCATION AND CONDITION, INCLUDING ANY EXISTING DAMAGE OR DEFICIENCIES.
13. ANY SIGNS AND POSTS BEING RE-USED ON THIS PROJECT SHALL BE STOCKPILED IN A MANNER TO AVOID DAMAGE AND MAINTAIN THE INTEGRITY OF THE SIGNS. SAFE STORAGE OF STOCKPILE AND PREVENT OF DAMAGE TO THE STOCKPILE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
14. ALL SIGNS AND POSTS NOT BEING RE-USED ON THIS PROJECT SHALL BE DISMANTLED, STACKED AND DELIVERED TO THE OWNER (CITY OR COUNTY) BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR THE SAFE STORAGE AT THE CONSTRUCTION SITE UNTIL DELIVERY AND THE SAFE UNLOADING OF THE SALVAGED MATERIAL. NOTIFICATION OF DELIVERY SHALL BE MADE AT LEAST 2 WORKING DAYS PRIOR TO DELIVERY. PINN COUNTY SIGN SHOP, PINN COUNTY SIGN SHOP 1303 S. MISSION ROAD (500) 724-2630. NO FRIDAY DELIVERIES.



Pin County Department of Transportation

Ariz M. Dienes, P.E., Director

DATE	
BY	
CHECKED	
DATE	
BY	
CHECKED	
DATE	
BY	
CHECKED	

SIGNING GENERAL NOTES

Project Name - Ariz Road to Ariz Road - Project No. 447004